



KEYED NOTES

- 1. PROVIDE NEW OPENING IN EXISTING WALL FOR NEW WOOD DOOR AND FRAME TO MATCH EXISTING.
- 2. PROVIDE NEW GYP. BD. CEILING @ 7'-0" (84") +/- A.F.F.; RELOCATE/EXTEND EXISTING HVAC AND LIGHTING FROM EXISTING CEILING TO NEW CEILING.
- 3. REMOVE AND RELOCATE EXISTING DOOR & FRAME AS SHOWN TO WALL BETWEEN ROOMS 285 & 286; CLOSE OPENING TO MATCH EXISTING WALL FINISH.
- 4. PROVIDE NEW DATA/PHONE AND ELECTRICAL OUTLET AS REQUIRED FOR NEW DESK LOCATION AND/OR FOR RELOCATED COPIER.
- 5. REMOVE EXISTING DOOR & FRAME AND INSTALL NEW DOOR AND FRAME WITH DOOR SWING AS SHOWN AND NEW DOOR HARDWARE; MATCH EXISTING FINISHES.
- 6. REMOVE SECTION OF EXISTING WALL; PATCH/REPAIR AND PAINT WALL TO MATCH EXISTING.
- 7. PROVIDE NEW OPENING IN EXISTING WALL FOR NEW WOOD DOOR AND FRAME, MATCH EXISTING; REMOVE AND RELOCATE ELECTRICAL OUTLETS TO ADJACENT WALL AS SHOWN.
- 8. REMOVE AND RELOCATE EXISTING DUTCH DOOR TO OFFICE 282. PROVIDE S.C. WOOD DOOR WHERE DOOR WAS REMOVED.
- 9. REMOVE EXISTING DOOR AND INSTALL RELOCATED DUTCH DOOR FROM OFFICE "A". PROVIDE NEW DUTCH DOOR IF RELOCATED DOOR DOES NOT FIT PROPERLY.
- 10. PROVIDE NEW S.C. WOOD DOOR TO FIT EXISTING DOOR FRAME. MATCH EXISTING.
- 11. MODIFY EXISTING WALL MOUNTED SHELVING AS NEED FOR NEW STORAGE ROOM.
- 12. PROPOSED LOCATION FOR RELOCATED COPIER.

FLOOR PLAN

1895 Courthouse 2nd Floor

SCALE: 1/8"=1'-0"



Tarrant County - Facilities Management
Construction Services

100 W. Weatherford St. Room 350
Fort Worth, Texas 76196
p: (817) 884-1502



OFFICE RENOVATIONS FOR
1895 COURTHOUSE 2ND FLOOR COURTROOM AREA

FLOOR PLAN, KEYED NOTES

DRAWN BY:
H.C.

DATE:
August 31, 2023

DWG. NUMBER
1895 CH 2nd Flr 8.31.23

SHEET NO.

A-1

SHEETS 1 OF 1